


OVERVIEW

The Ground Frame Foundation System provides a solid, stable, and efficient foundation that captures and preserves the supporting strength and natural functions of the Earth's soil and provides connection to the structure above.

IMPORTANT NOTE:

- Ensure all permits have been obtained.
- Check for buried utilities, mark on site as per local building codes.
- Have all required tools and equipment outlined on page 4.
- Wear proper personal protective equipment (PPE).



Horizontal Pipe Distance


Measured from horizontal center of anchor bolt to vertical pipe end limit

| Pipe Length (Inches) | Horizontal Pipe Distance (inches) |
|--------------------------------|---|
| | Pipe at 90 degrees Perpendicular to limit plane |
| 50 | 29 |
| 63 | 38 |
| 84 | 51 |






GROUND FRAME BEAM AND L-BRACKET CONNECTOR OVERVIEW



GROUND FRAME BEAM AND COPED CONNECTOR OVERVIEW







Weld Block Connector

GROUND FRAME SMART PART NUMBERS

Simplify field inventory checks using our smart part numbers.

| Ground Frame B= Beam C=Column 2"Standard* Beam Lengths 21" Beam Lengths 21" | s: 21" | 50" 63" 84" 2" Pipe Note: 2 3/8" actual 2" | L-Bracket Connector Adjustable Connector |
|--|---|--|--|
| SUGGESTED CREW AND TOOLS | | pipe dimension. | |
| | | | |
| Three-person crew Site transit leve for beam installation, | Electric driving hai (60 lb or greater) | nmer Sledgehammer o with post driver | r Small level with magnetic edge |
| two-person for column | driving bit | | Contra Solution |
| | Square-edge shovel required for column | Steel Stake (36" length) (Use for batter boards and | 2 Pipe Wrenches (Use heavy duty pipe wrenches |
| Ratcheting wrench | installation | for plumbing beams) | that will go over the outside diameter of the pipe) |
| | | | |


1

Driving log Note: Download template at groundframes.com



| Do | Don't |
|---|---|
| Follow the instructions in this guide. | Proceed without reading this guide. |
| Use only specified hardware. | Substitute hardware |
| Review troubleshooting tips to safely remove pipes or adjust pipes. | Force pipes past obstructions |
| | Weld directly to the beam. Beam is galvanized and has structural integrity, never weld directly to the beam. Always use provided parts such as a weld block as your welding surface. |

BEFORE YOU BEGIN Check Pipes for Proper Slide



Anchor bolt

B Force plate

C Driving holes side and base The anchor bolt and force plate are factory set for proper pipe slide, but may have altered during shipping and handling.

Pipes should easily slide through holes. If pipes do not easily slide, loosen locking bolt. **Do NOT force** the pipes through the beam/ column holes.


If the bolt is fully loosened and the pipes do not easily slide, contact Ground Frame customer service.



SITE PREPARATION




1. Clear and level site as per approved plans. Ensure proper site drainage and desired floor height.






2. Using the dimensioned layout as a guide, establish the building border with a string line.



3. Measure diagonally to ensure the border is squared.



4. Find the elevation of a "Master Corner" (the highest corner).



5. Using the dimensioned layout, roughly stage the Ground Frame steel beams. It is best practice to start in the corners.






6. Block and shim the end of steel beams to the same level as the master corner. Minimum block height is 1" for frost heave.



7. Maximum block height is 4". Ensure driving holes remain open and are not blocked by shims.



8. Verify all outer dimensions according to the dimensioned layout.Ensure steel beams are plumb, level, and square to the overall layout.Upon leveling completion, gather and stage Ground Frame pipes.




Best practice is to cradle the beam with 4 stakes to ensure it stays on layout when driving pipes.




PIPE INSTALLATION

Ground Frame strongly recommends using a two-person crew for pipe driving. **Ground Frame pipes are not refusal driving systems**. All pipes must be driven to their full length to provide specified bearing, uplift and lateral capacities.



C Driving holes side and base



9. Ensure the pipe can easily slide through the side driving hole. **Important Note:** If pipe does not easily slide, loosen the nut (on top of beam), lowering the force plate.




10. To ensure the pipe maintains the proper angle, hold it against the upper ellipse of the side driving hole.



11. Using a sledgehammer, drive the pipe in a few inches, to maintain the proper angle.





12. Prepare the driving log. **Note:** Download template at groundframes.com




13. While holding the pipe up, drive the pipe through the side driving hole, using the jackhammer with the pipe driving bit.

Note: Recommend using the Hilti TE-3000 AVR electric jackhammer for driving pipes.



14. Stop driving prior to bit hitting the beam.



15. After each pipe installation note time in driving log, using beam schedule.





16. When pipe hits an obstruction, follow the troubleshooting steps found on page 10.



17. Install pipe caps on top of each pipe.

Cripple walls or pedestals may be required based on your site conditions. **These must be designed, engineered and approved.**




Installation Instructions Modular



TROUBLESHOOTING

SHALLOW OBSTRUCTION: ~1/3 Pipe Length in the Ground





1. Remove pipe.

3. Redrive pipe.


Tip: Simultaneously spin and pry pipe, using two pipe wrenches with two people.

2. Remove obstruction and recompact soil in 6" lifts.

DEEP OBSTRUCTION: 2/3 Pipe Length in the Ground



1. Using a sledgehammer, strike the pipe, 3-5 blows, to ensure pipe refusal.





2. Cut the remaining portion of the pipe, above the Ground Frame beam, and cap. **Important Note:** Indicate the length of the pipe that was cut off in the driving log.

